

Appendix 1

Devolved Community Council Funded Schemes

Community Council : **Dulwich**

Date: **13 January 2012**

Funding	
Under spend from 2011 -12	£64,257.24
Allocation for this year	£100,000.00
Total available	£164,257.24

Officer Recommendations

Candidate Road	Ward	Identified defects	Suggested treatment	Estimated Cost
Asbourne Grove	East Dulwich	Carriageway : Localised surface degradation and failings of sections of the carriageway between sinusoidal speed humps and around gullies. Signs of local failure at sub-base level.	Carriageway : Plane off and resurface (40mm) sections between humps. (NB: Might be more viable to remove speed humps > resurface > reinstate humps); reinstatement of road marking.	£53,000.00
Chesterfield Grove	East Dulwich	Carriageway : Localised surface degradation and failings of sections of the carriageway between sinusoidal speed humps and around gullies. Signs of local failure at sub-base level.	Carriageway : Plane off and resurface (40mm) sections between humps. (NB: Might be more viable to remove speed humps > resurface > reinstate humps) ; reinstatement of road marking.	£36,300.00
College Rd	College	Carriageway : Localised depressions suggesting sub base / grade failing; repeated patching in various states of degradation; rutting ; longitudinal and transverse cracking	Carriageway : Plane off and resurfacing 40-100mm plus some full depth reconstruction in places ; reinstatement of traffic calming and road marking.	£64,000.00
Seeley Drive	College	Carriageway : Local deformations; potholes; Irregular cracking ;	Carriageway : Plane off and 40mm resurfacing ; reinstatement of 2 speed humps and road marking.	£38,400.00
Colby Rd	College	Carriageway : Localised failings ; kerbstones dislodged near some trees ; severe longitudinal failure. (NB : Access to Colby Rd Nursery needs to be considered) Footway : Uneven northern footway approx 70m long with extensive trenching and patching near intersection with Dulwich Wood Avenue; some cracking due to tree roots	Carriageway : Plane off and resurface (40mm) near intersection with Dulwich Wood Avenue due to low existing kerb upstand ; reinstatement of road marking. Footway : Relay with flexible surfacing and roll over sections near proud tree roots	£27,000.00 £5,000.00
Roseway	Village	Carriageway : Local depressions and failings from degradation ; alligator cracking	Carriageway : Plane off and resurfacing 40mm with some channel reprofiling	£21,000.00