

## Appendix 2

\* The schemes below were proposed as potential locations for consideration from a walkabout on 11 January 2012 between Village ward councillors and council's highways engineers.

### Devolved Community Council Funded Schemes

Community Council : Dulwich – Village Ward

Date: 13 January 2012

Candidate Road	Ward	Identified defects	Suggested treatment	Estimated Cost
Townley Road (Outside No.27 - No.47)	Village	<b>Carriageway</b> : Areas have failing trench reinstatements and some surface degradation	<b>Carriageway</b> : Plane off and resurface sections between Property No 27 to 47.	£18,000.00
Townley Road (Outside No.73)	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£3,000.00
Townley Road (Outside No.105 –No 115)	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£22,000.00
Townley Road (Barclays to JW Woodyard Lane)	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£14,000.00
Townley Road (Outside No.188 )	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£1,500.00
Turney Road (Outside No.87 – No.89 )	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£2,000.00
Turney Road (Outside No.140 – No.142 )	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£2,000.00
Turney Road (Outside No.63 – No.65 )	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£2,000.00
Croxted Road (Outside No. 224 to Bus Stop)	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£10,000.00
Croxted Road (Outside No. 276 – No. 278)	Village	<b>Footway</b> : Uneven footway with extensive trenching and patching; some cracking due to tree roots	<b>Footway</b> : Relay with flexible surfacing and roll over sections near proud tree roots	£5,000.00

### Appendix 3

#### Devolved Community Council Funded Schemes

##### Update of Previous Schemes - 2011-12

Location	Description of Project	Ward	Allocation	Total Cost of Works	Balance Remaining	Started	Completed	Comments
Howletts Road	Carriageway Resurfacing	Village	£30,000.00	£5,426.24	£24,573.76	May-11	May-11	Completed - works undertaken under planned maintenance programme
Warmington Road	Carriageway Resurfacing	Village	£30,000.00	£23,649.52	£6,350.48	Sep-11	Sep-11	Completed
Potholes	Carriageway (Potholes)	Village	£3,000.00	£3,000.00	£0.00	various	various	completed
Bowen Drive	Carriageway Resurfacing	College	£45,000.00	£45,000.00	£0.00	Sep-11	Nov-11	completed