



Existing surface to be overlayed in 20mm of mastic asphalt

Existing gully situated within proposed parking bay to be capped

New gully to be installed on carriageway adjacent to parking bay

Parking bay marking in accordance with TSRGD 1028.4

Existing surface to be overlayed in 20mm of mastic asphalt

Proposed parking bay to be reinforced with concrete and infilled with 240mm x 160mm mistral blocks

Parking bay sign to be removed

Footway to be extended into carriageway, infilled and surfaced with mastic asphalt. New 150mm granite kerbs to be installed with kerb radii returns of 1m

Proposed tree pit to be installed with 160mm x 160mm silver grey mistral set edging (1280mm length)

New gully to be installed at southern end of footway buildout

Proposed 50mm thick double yellow line marking in accordance with TSRGD 1018.1

Bollards to be removed

Footway to be extended into carriageway, infilled and surfaced with mastic asphalt. New 150mm granite kerbs to be installed with kerb radii returns of 1m

Proposed tree pit to be installed with 160mm x 160mm silver grey mistral set edging (4000mm length)

New gully to be installed at southern end of footway buildout

Bollards to be removed

Junction give way markings to be installed TSRGD 1003 and 1004. Give way markings to follow curvature of adjacent flush kerbline

Proposed 50mm thick double yellow line marking in accordance with TSRGD 1018.1

Carriageway to be resurfaced with 10mm HRA in accordance with proposed levels on drawings LS/13/001/2

Kerbline to be broken out and new 150mm silver/gray granite kerbs installed to proposed level

Existing footway to be regulated to proposed levels (fixed backline) and overlayed with mastic asphalt. Refer to drawings LS/13/001/2 for proposed levels

Existing tactile paving to be removed and new buff colour tactile installed to new levels

	Proposed flush carriageway kerb		Proposed tree pit (1280mm x 1280mm boarded with 160mm x 160mm mistral blocks)
	Proposed gradient transition kerb section		Proposed mistral 240mm x 160mm blocks (for parking bay)
	Proposed new 150mm granite kerb		Proposed yellow line marking
	Existing kerbline to be broken out / removed		Proposed white line marking
	Proposed gully position		Area of carriageway to be excavated and converted to footway with mastic asphalt surfacing
	Existing gully to be removed		Existing footway area to be overlayed in mastic asphalt
	Existing gully		Area of carriageway to be resurfaced
	Existing sign and post to be removed		Bollard to be removed
	Proposed new position of sign and post		
	Sign / post to be relocated		
	Proposed new position of lamp column		

Shaping Southwark's Highways

PUBLIC REALM PROJECTS TEAM
 ENVIRONMENT AND LEISURE
 160 TOOLEY STREET
 SE1P 5LX

No.	Date	Revision
	5/13	

Project

Alice Street Streetscape Improvements

Title

General Arrangement

Contract No.	Drawn	CM
Scale	Designed	CM
1:100 @ A1	Checked	QK
Approved	Approved	QK
Drawing No.	Rev.	A
AS/GA/13/001		
Date Drawn	Date Issued	
5/13		