NOTES:

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER SOUTHWARK COUNCIL DRAWING SCHEME No. 12108 AS LISTED ON THE DRAWING ISSUE SHEET.
2. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE STATE.
3. DO NOT SCALE FROM THIS DRAWING, USE ONLY WRITTEN DIMENSIONS.
4. ANY DISCREPANCIES TO BE REPORTED TO THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.
5. THE POSITION OF ANY UNDERGROUND UTILITIES SHALL BE VERTIFIED AND ESTABLISHED ON SITE BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
6. ALL AFFECTED SERVICES WITHIN THE AREA OF WORKS TO BE RELEVELLED TO NEW FOOTWAY/CARRIAGEWAY PROFILE.
7. RISK OF UNDERMINING LAMP COLUMN FOUNDATIONS. TAKE EXTRA CARE WHEN DOING FOOTWAY EXCAVATIONS.
8. PROPOSED TABLES TO BE 75mm IN HEIGHT ABOVE EXISTING ROAD FORMATION, UNLESS OTHERWISE SPECIFIED.
9. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH SERIES 1100 OF VOL. 2 ANNEX C - LOT B PROJECT DELIVERY (WORKS).

KEY:

- EXTENT OF WORKS
- PROVIDE AND LAY SFA 30MM THICK ON BiFA 40MM THICK ON CBGM B, C8/10 150MM THICK.
- PROVIDE AND LAY F-PC-B1(70) IN ORTHAGONAL STRETCHER BOND 2-4MM WIDE J-SS1 JOINTS ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- PROVIDE AND LAY PRECAST CONCRETE BLOCK (MISTRAL) - UPPER FACE AREA ≤ 0.04SQM. IN ORTHAGONAL STRETCHER BOND - 2-4MM WIDE J-SS1 JOINTS ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- PROVIDE AND LAY B-PC(80)-B1d IN 45° HERRINGBONE BOND - 2-4MM WIDE J-SS1 JOINTS ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- REMOVE FROM SET ASIDE AREA AND LAY PRECAST CONCRETE BLOCK (MISTRAL) - UPPER FACE AREA ≤ 0.04SQM IN ORTHAGONAL STRETCHER BOND 2-4MM WIDE J-SS1 JOINTS ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- REMOVE FROM SET ASIDE AREA AND LAY PRECAST CONCRETE BLOCK - UPPER FACE AREA ≤ 0.02SQM IN ORTHAGONAL STRETCHER BOND 2-4MM WIDE J-SS1 JOINTS ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- PROVIDE AND LAY T (B) - PC 3, BLISTER TACTILE PRECAST CONCRETE PAVING FLAG (RED) ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- PROVIDE AND LAY T (B) - PC 4, BLISTER TACTILE PRECAST CONCRETE PAVING FLAG (BUFF) ON SPECIFIED FOOTWAY CONSTRUCTION DETAIL.
- PROPOSED TREE PIT EXTENTS. EXCAVATION WORKS AROUND EXISTING TREES TO BE CARRIED OUT IN ACCORDANCE WITH VOL.4 OF THE NJUG GUIDELINES.
- EXISTING IRONWORK COVER AND FRAME TO BE ADJUSTED TO MATCH NEW LEVELS IN FOOTWAYS AND CARRIAGEWAYS.
- PROVIDE AND INSTALL K15-T1(N/S) OR K15-T1(N/R) WITH OUTER FACE RADIUS OF 3M OR 4.5M - UNITS SILVER GREY.
- REMOVE FROM SET ASIDE AREA AND INSTALL ANY NATURAL STONE STRAIGHT KERB, WIDTH ≤ 300MM.
- PROVIDE AND INSTALL K15-T1(U/S) OR K15-T1(L/R) WITH OUTER FACE RADIUS OF 3M OR 4.5M - UNITS SILVER GREY.
- PROVIDE AND INSTALL K15-T1(N/S-D1) and K15-T1(N/S-D2) - UNITS SILVER GREY.
- PROVIDE AND INSTALL SURFACE WATER DRAIN PIPE GROUP 6, 150MM INTERNAL DIAMETER DEPTH TO INVERT ≤ 2M, AVERAGE DEPTH OF 750MM ON BED TYPE Z.
- PROVIDE AND INSTALL SERVICE DUCT IN CARRIAGEWAY OR FOOTWAY PIPE GROUP 1 IN TRENCH DEPTH TO INVERT ≤ 2 METRES, AVERAGE DEPTH TO INVERT 500 MM.
- PROVIDE AND INSTALL SERVICE DUCT IN FOOTWAY PIPE GROUP 10 IN TRENCH DEPTH TO INVERT ≤ 2 METRES, AVERAGE DEPTH TO INVERT 500 MM.
- G PROVIDE AND INSTALL PRECAST CONCRETE TRAPPED GULLY, WITH TYPE D COVER, GULLY DEPTH ≤ 750MM.
- EXISTING GULLY CHAMBER TO BE RAISED TO MATCH NEW LEVEL AND PLATED WITH MANHOLE COVER AND FRAME.

No.	Date	Revision
A	08/13	INITIAL ISSUE

Southwark Council
PUBLIC REALM PROJECTS, HOUSING & ENVIRONMENT
COUNCIL OFFICES, 160 TOOLEY STREET, LONDON SE1 5LX

DRAFT

Project: EAST DULWICH GROVE

Title: KERBS & FOOTWAYS
SHEET 2 OF 3

Contract No.	-	Drawn	KA
		Designed	DV
Scale	SCALE: 1:200 @A1	Checked	-
		Approved	-
Drawing No.	12108/1100/002	Rev.	A
Date Drawn	08/2013	Date Issued	05/08/13

Based upon the Ordnance Survey 1:1250 mapping with the permission of the Controller of Her Majesty's stationery office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. On behalf of London Borough Of Southwark. Licence No. 0100019252.