Notes:

1. This drawings is to be read in conjunction with all other relevant Conisbee civil engineering drawings.
2. All road markings and signs are to be installed in accordance with the DfT Traffic Signs Manual - Chapter 5 : 2003
3. All road markings and signs are to be in accordance with the Traffic Signs and Regulations and General Directions (TSRGD) 2002 and its Amendments No,1 and No, 2 dated 2011.
4. Illumination of signs is to be in accordance with the TSRGD schedule 17 and the requirements of the local Highway Authority.
5. All proportions and form of letters, numerals and other characters are to be in accordance with schedule 13 of the TSRGD.
6. All street furniture except lighting columns should be set a minimum of 500mm from the kerb face.
7. Road markings shall be installed using reflectorised paint in accordance with regulation 31 of the TSRGD.
8. Final locations of all signs are to be confirmed by the relevant highway authority prior to installation, Road names for the development are to be confirmed once agreed with London Borough of Southwark Council

LEGEND

- Street nameplate
- Road sign and post (to LBS Specification)
- Street light lamp column
- Permanent Bollards

Rev	Date	Description	Drawn	Check
C2	08,10,13	Highway Technical Approval Submission	SK	AW
C1	28,06,13	S38 / S278 Highway Submisison	AW	AW

conisbee
Consulting Structural Engineers
Consulting Civil Engineers
1-5 Offord St
London N1 1DH
Tel 020 7700 6666
Fax 020 7700 6686
design@conisbee.co.uk
www.conisbee.co.uk

Drawing Status: CONSTRUCTION

Project: AYLESBURY ESTATE SITE 7

Title: HIGHWAY WORKS SIGNS AND ROAD MARKINGS

Date: JUNE 2013
Scale: 1:200@A1
Drawn: SK
Engineer: AW
Project No: 110576
Drawing No: C307
Revision: C2

THIS DRAWING MUST BE READ IN CONJUNCTION WITH THE SPECIFICATION AND ALL OTHER RELEVANT DRAWINGS. DO NOT SCALE FROM THIS DRAWING.

APPENDIX 1