ISO FULL BLEED A3 420 X 297 MM

PTS 10
LIMIT OF WORKS
28m length resurfacing from stop line north side carriageway.
Carriageway regulating and resurfacing
Diag 1062
Diag 1055.1
Diag 1001.5
Diag. 1017
Diag. 1018
Diag. 1004
Zig-Zag markings
Diag. 1001.4
Diag. 1018
Diag. 1017
Diag. 1004
Diag. 1017
Diag. 1018
Diag. 1018
Diag. 1017
6.00
6.00
2.85
PTS 11 & 12
PTS 13 & 14
PTS 09
ETS 08
ETS 09
ETS 10
ETS 11a & 11b
PTS 03, 04 & 05
PTS 06, 07 & 08
ETS 13
See Drawing numbered LBS/MW/LLWILDS-RENTS/700-01 for carriageway resurfacing
Diag. 1018
Diag. 1018
Cut Line 1
ETS 12
PTS 11a & 11b
Diag. 1017
ETS 01,02, 03 &04
PTS 01
Diag 1009
1004
Graduate
PH
4 to 7
ELIM ST
WILD'S RENTS
219
218
226
230
208
22
Diag. 1018
Diag. 1018
Cut Line 1
ETS 12
PTS 11a & 11b
Diag. 1017
ETS 01,02, 03 &04
PTS 01
Diag 1009
ETS 05, 06 &07
PTS 02
Diag. 1004
LIMIT OF WORKS
3 to 8

NOTES

1. Dimensions in meters, unless otherwise stated.
2. This drawing should be read in conjunction with other relevant engineering details, drawings & specifications.
3. Any discrepancies should be reported to the design engineer immediately, so that clarification can be sought prior to the commencement of works.
4. The dimensions must be verified on site before construction.
5. All works are to be in accordance with Southwark borough council specification and standards.

KEY

NEW PCC 600x600X63
PCC paving slabs. Area: 270 sqm. For detail see CDX on dwg. no. LBS/MW/GIBBON-ROAD/900-1100/01

CORDUROY PAVING
Corduroy paving. For detail see CDX on dwg. no. LBS/MW/GIBBON-ROAD/900-1100/01. Area 7.5 sqm.

T(B) - PC(65)
Blister tactile paving precast concrete paving - Dark Grey. Area: 12 sqm.

GRANITE SETTS AROUND TREE PIT
Granite setts 80x80. Area: 2 sqm.

150X300mm GRANITE KERB
New granite kerb.laid with 125mm upstand. Length: 135m. For details see CDX on dwg. no. LBS/GIBBON-ROAD/900-1100/01

150X300mm GRANITE KERB
New granite kerb.laid flush. Length: 15 m. For details see CDX on dwg. no. LBS/GIBBON-ROAD/900-1100/01

150X300mm GRANITE KERB
New granite kerb taper kerb. Length: 12 m. For details see CDX on dwg. no. LBS/GIBBON-ROAD/900-1100/01

TRAFFIC SIGN
Take down traffic sign board and remove to tip (x no.). Retain post.

TRAFFIC SIGN
Take up down traffic sign board and post and remove to tip. (x no)

TRAFFIC SIGN
TProposed new traffic sign board and post (x no.)

ROPOSED ROAD MARKING
Proposed/Refreshed road marking

BELISHA BEACON
Bellisha Beacon. Quantity 2 no.

PROPOSED BOLLARD
Proposed new Manchester Cast Iron Bollard. Colour: Black . Quantity 8 no.

PROPOSED GULLY
Proposed new carriageway gully. Quantity 2 no.

EXISTING GULLY
Existing road gully retained

REV	DATE	REVISION DESCRIPTION / DETAILS	DRN BY	CHKD BY	APRVD BY
--	--	--	--	--	--

Southwark Council
southwark.gov.uk
160 TOOLEY STREET LONDON SE1P 5LX

PROJECT: LONG LANE WILD'S RENTS ZEBRA CROSSING

TITLE: GENERAL ARRANGEMENT

STATUS: DD		DRAWN	AK
		DESIGNED	AK
SCALE: 1:250 @ A3		CHECKED	GM
		APPROVED	RW
DRAWING NO: LBS/MW/LLWILDS-RENTS/GA-01		REV: --	
DATE DRAWN: 05 DECEMBER 2023	DATE ISSUED: --		

\\LBS.SH-CHA-AS1\S1\SHARE\TRANSPORT PROJECTS\MINOR WORKS\CIL FUNDED SCHEME\S21-22\LONG LANE-WILD RENTS CROSSING\01 PROJECT DETAILS\02 PLANS AND DRAWINGS\DETAILED DESIGN\LBS-MW-LLWR-0100-GA.DWG